

Sl. No.	Items of work	Per	Quantity	Rate	Rate in words
9.	Teak wood wrought and put up, etc., complete with wood oiling.	C.ft.	140.20		
10	Providing burnt stone slabs pillars of 1' wide 6" thick and 9½' height with dressing, cutting groove at top to receive bressemer, etc., complete, including fixing.	Each	6		
11	Plastering with chunam mortar, two coats ...	Sqr.	26.20		
12	Roofing with first class Mangalore tiles on teak reapers, etc., complete with wood oiling to reapers, etc.	"	14.54		
13	Ridge tiles set in mortar	R.ft.	41½		
14	Chunam borders over roof	"	71		
15	Flooring with Cuddapah slabs of 1½" thick over 3" concrete and cement pointing, etc., complete.	Sqr.	8.30		
16	White washing 2 coats	"	26.20		
17.	Expanded metal 3" mesh with teak frames of 2"×2" including fixing and painting, etc., complete (slate colour).	S.ft.	413		
18	Cement pointing to Basement	Sqr.	1.90		
19	Teak wood Eave board 1" x 9" wide ordinary including (slate colour) painting two coats, etc., complete.	R.ft.	146		

M. A. SRINIVASACHARI,
Executive Engineer.

MYSORE DIVISION.

Abstract Notification, dated 20th July 1933.

The attention of the public is invited to the detailed notification of 20th July 1933, regarding the sale of an old Public Works Department Sub-Division Office Building at Hunsur, published on page 923 of Part VI of the *Mysore Gazette*, dated 27th July 1933.

K. NABAYANA IYENGAR,
Executive Engineer.

KOLAR DIVISION.

Notification, dated 31st July—1st August 1933.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M., 28th August 1933, for the work of opening a feeder channel to the Minakankurki Tank Reg. No. 88 of Goribidnur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of 15th June 1935.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of two hundred and eighty-five only in cash or Government Currency as earnest money, and be superscribed "Tender for the work of opening a feeder channel to Minakankurki Tank, Regd. No. 88 of Goribidnur Taluk," in default of which the tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates should be entered both in words and figures.

Abstract of the probable cost of opening a feeder channel to the Minakankurki Tank Reg. No. 86 from a jungle stream of Goribidnur Taluk.

Item No.	Details of work	Quantity	Per	Rate	Amount
				Rs. a. p.	Rs.
1	Excavating channel in chillu soil ...	3,726	C.yd.	0 8 0	1,868
2	Do in soft rock ...	3,870	"	0 10 0	2,419
3	Benching hard rock to the level of the bed of jungle stream in front of anicut.	300	S.ft.	0 8 0	150
	Total ...	...	..	...	4,432
	<i>Anicut.</i>				
1	Excavating foundation in hard gravelly soil ...	28	C.yds.	0 6 0	10
2	Do in soft rock ...	14	"	0 10 0	9
3	Filling in foundation concrete in surki mortar.	160	C.ft.	0 4 6	45
4	Masonry:—Burnt stone in surki mortar ...	829	"	0 5 6	285
5	Burnt stone slabs 6" thick dressed ...	192	S.ft.	0 6 0	72
6	Pointing with surki mortar ...	10'30	Sqr.	2 8 0	26
7	Apron filling in jelly ...	15	C.yd.	0 8 0	8
8	New rough stone work ...	29	"	1 2 0	33
9	Draft clearing, down stream side, hard chillu soil.	52	"	0 8 0	26
10	Forming embankment on both of Arms of anicut, with earth, consolidation and revetment, etc.	Lumpsum		...	99
11	Providing joints for coping slabs ...	"	"	..	10
	Total ...	...	...	..	628
	<i>Acqueduct.</i>				
1	Earth work excavation in chillu soil ...	25	C.yd.	0 8 0	13
2	Filling in foundation concrete in surki mortar.	230	C.ft.	0 4 6	65
3	Masonry:—Burnt stone in surki mortar ...	240	"	0 5 6	82
4	Burnt brick in surki mortar ...	625	"	0 5 6	215
4a	Burnt stone in surki mortar ...	625	"	0 5 6	215
5	Burnt stone slab 6" thick dressed ...	522	S.ft.	0 6 0	196
6	Cut stone pillars 1' x 1' thick dressed ...	57	C.ft.	1 0 0	57
7	Plastering with surki mortar ...	10'28	Sqr.	4 0 0	42
	Total Nos. 1, 2, 3 items 4432+628+670=Rs. 5,730.	...	...	...	670

Notification, dated 31st July—1st August 1933.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 30th August 1933, up to 2 p.m. for restoring Vangimallu Tank Registered No. 195 of Chintamani Taluk. An approximate estimate of quantities is

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms, which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees four hundred and fifty in cash or Government Currency Notes as earnest money and be superscribed "Tender for Restoring Vangimallu Tank, Registered No. 195 of Chintamani Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates should be entered both in words and figures.

Detailed abstract estimate of the probable cost of Restoring Vangimallu Tank, Registered No. 195 of Chintamani Taluk.

No.	Items of work	Per	Quantity	Rate	Amount
<i>Bund.</i>					
				Rs. a. p.	Rs.
1	Jungle clearing prickly pier ...	Grade	25	3 0 0	75
2	Earth work to bund including watering and Tamping:	C.yds.	4,169	0 4 0	1,042
3	Earth work excavation foundation for revetment.	"	647	0 3 0	121
4	Gravel backing ...	"	584	0 8 0	292
5	Turfing ...	S.yd.	3,758	0 1 0	235
6	New stone revetment as per statement	C.yd.	2,152	1 12 0	3,766
7	Resetting old stone with new jelly	"	409.42	0 12 0	307
8	Providing and fixing grade stones with cutting figures and painting complete.	Grade	25	1 8 0	38
9	Providing and fixing Reg. No. Stones do	No.	1	2 0 0	2
10	Providing year and date stone do	"	1	2 0 0	2
11	" Gauge stone do	"	1	15 0 0	15
12	Bench mark stones do	"	2	2 0 0	4
13	" Index stones do	"	25	0 4 0	6
14	Inscription stone	"	1	50 0 0	50
Total Rupees for bund				...	5,955
<i>Sluice No. 1.</i>					
1	Earth work cut opening the bund including cutting grips.	C.yd.	208	0 3 0	39
2	Excavating foundation	"	7	0 3 0	1
3	Filling foundation with Surki concrete	C.ft.	151	0 4 6	42
4	Burnt brick in Surki mortar or	"	229	0 5 0	90
4(a)	Stone in surki mortar	"	229	...	...
5	Burnt tone slab 3" thick	S.ft.	102	0 3 6	22
6	" 6" " roughly dressed	"	94	0 5 0	29
7	Cutting holes in slabs.	No.	4	0 8 0	2
8	Plastering Surki mortar	Sqr.	4.32	4 0 0	17
9	Earth work refilling as per excavation and allowing for settlement.	C.yd.	229	0 3 0	48
10	Providing angle iron 2" x 2 x 1/2" with wooden plug and locking	Each	1	20 0 0	20

No.	Items of work	Per	Quantity	Rate	Amount
	<i>Constructing a masonry waste weir left.</i>			Rs. a. p.	Rs.
1	Earth work excavation foundation in soft soil.	C.yd.	150	0 3 0	28
2	Concrete in surki mortar	C.ft.	267	0 4 6	75
3	Burnt brick in surki mortar or	"	1,019	0 5 0	318
3(a)	Stone in surki mortar	"	1,019	0 5 0	...
4	Burnt stone slab 6" thick roughly dressed	S.ft.	210	0 5 0	66
5	Surki mortar plastering	C.yd.	10'80	4 0 0	43
6	Rough stone work new	"	101	1 12 0	177
7	Providing joggles	Each	20	0 12 0	15
	Total Rupees waste weir	...	...	...	722
	<i>Constructing a masonry waste weir 200 ft. right.</i>				
1	Earth work excavation foundation (hard soil).	C.yd.	692	0 5 0	216
2	Concrete in surki mortar	C.ft.	552	0 4 6	155
3	Burnt brick in surki mortar or	"	1,276	0 5 0	399
	Stone in surki mortar	"	1,276	...	...
4	Burnt stone slab 6" thick roughly dressed	S.ft.	540	0 5 0	169
5	Surki mortar plastering	Sqr.	13'69	4 0 0	55
6	Rough stone work new	C.yd.	256	1 12 0	448
7	Providing joggles	No.	33	0 12 0	25
	Total waste weir right	...	...	...	1,467
	<i>Channel.</i>				
1	Improving the feeder channel to the Tank	Lumpsum		..	500
	Total Rs.	..	...	...	8,949

N.B.—When trees are cut, roots should be completely removed.

Notification, dated 31st July—1st August 1933.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 30th August 1933, at 2 P.M. for Restoring Thimmanai-kanahalli, Nagalkere, Registered No. 96 of Sidlaghatta Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of 15th June 1935.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar between the hours of 11 A.M. to 5 P.M.

3. The tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees four hundred and thirty in cash or Government Currency Notes, as earnest money and be superscribed "Tender for Restoring Thimmanai-kanahalli Nagalkere, Registered No. 96 of Sidlaghatta Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual Contract Bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

Abstract of estimate of the probable cost for Restoring Thimmanaikanahalli, Nagalkere, Registered No. 96 of Sidlaghatta Taluk.

No.	Items of work	Per	quantity	Rate	Amount
<i>Bund.</i>					
1	Earth work including watering and tamping.	C.yd.	11,420	0 4 0	2,855
2	Turfing	S.yd.	6,329	0 1 0	395
3	Resetting old stone revetment with new jelly.	C.yd.	711	0 12 0	533
4	New stone work	"	1,065	2 0 0	2,130
5	Providing and fixing new grade stones including figuring and painting complete.	No.	29	1 8 0	43
6	Do Index stones, painting complete.	"	29	0 8 0	14
7	Do Bench mark stones do	"	2	3 0 0	6
8	Do Register No. stones do	"	1	3 0 0	3
9	Do Gauge stones do	"	1	15 0 0	15
10	Clearing jungle, cutting, rooting out trees and removing ant hills, etc.	Grade	28	10 0 0	280
Total to bund Rs.					6,274
<i>Sluice No. 1.</i>					
1	Earth work excavation	C.yd.	47	0 4 0	12
2	Refilling gap with watering and Tamping	"	26	0 4 0	7
3	Burnt brick in surki mortar or	C.ft.	263	0 5 0	82
3(a)	Stone in surki mortar	"	263	...	...
4	Burnt stone slab 6" thick roughly dressed	S.ft.	22	0 6 0	83
5	Surki mortar plastering	Sqr.	3 96	4 8 0	18
6	Providing plug and rod with locking arrangement.	Lumpsum		...	20
7	Concrete in surki mortar	Cft.	173	0 4 6	49
8	Drilling holes and cutting grooves	Lumpsum		...	10
Total sluice					281
<i>Sluice No. 2.</i>					
1	Details as in Sluice No. 1	Lumpsum		...	281
Total of Sluice Nos 1 and 2					562
<i>Waste weir.</i>					
1	Earth work Excavation	C.yd.	425	0 4 0	106
2	Surki concrete	C.ft.	640	0 4 6	180
3	Burnt brick in surki mortar or	"	1,896	0 5 0	593
3(a)	Stone in surki mortar	"	1,896	...	...
4	Burnt stone slabs 6" thick	S.ft.	772	0 6 0	289
5	Surki mortar plastering	Sqr.	23 82	4 8 0	107
6	New stone work	C.ft.	263	2 0 0	526
Total waste weir					1,801
Total bund, sluice and waste weir Rs.					8,637

N.B.—Cutting trees includes removal of roots.

Notification dated 31st July—1st August 1933.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 4th September 1933, up to 2 P.M. for Improving the Gotti-

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees three hundred and sixty only in cash or Government Currency Notes, as earnest money, and be superscribed "Tender for Improving the Gottikere Regd. No. 273 of Srinivasapur Taluk in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders, will be returned.

9. Rates should be entered both in words and figures.

Abstract of cost of Improving Gottikere Tank, Regd. No. 273 of Srinivasapur Taluk.

No.	Items of work	Per	Quantity	Rate	Total
	<i>Bund.</i>			Rs. a. p.	Rs.
1	Earth work including watering and tamping ...	C.yds.	11,119	0 4 0	2,780
2	Turfing ...	S.ft.	554	0 10 0	346
3	Rough stone pitching new ...	S.yd.	5,087	0 8 0	2,543
4	Jungle clearing ...	Each Grade	30	5 0 0	150
5	Providing and fixing grade stones, cutting figures and painting complete, etc.	Each	31	1 8 0	43
6	Providing and fixing index stones cutting figures and painting complete, etc.	"	31	0 8 0	16
7	Providing and fixing number and date stones, cutting figures and painting complete, etc.	"	1	3 0 0	3
8	Providing and fixing gauge stones, cutting figures and painting complete, etc.	"	1	15 0 0	15
9	Providing and fixing bench mark stones, cutting figures and painting complete, etc.	"	2	3 0 0	6
	Total Rs. to Bund ..	..	..	..	5,905
	<i>Sluices 1 and 2.</i>				
1	Repairing the existing sluice and building a new sluice in C. S. 12...	Lumpsum	"	...	350
	Waste weir 148 feet long:—				
1	Dismantling the old masonry ..	Lumpsum		...	5
2	Earthwork excavation ..	C.yd.	151	0 3 6	33
3	Masonry burnt brick in surki mortar, or	C.ft.	810	0 4 6	228
3a	Stone in surki mortar ..	..	810	..	..
4	Plastering surki mortar ..	Sqr.	1690	4 0 0	68
5	Burnt stone slabs 4" to 6" thick and well dressed	S.ft.	479	0 6 0	180
5a	Do do old ..	"	105	0 2 0	13
6	Rough stone work new ..	C.yd.	191	1 12 0	334
7	Resetting old stone with new jelly ..	"	97	0 12 0	73
8	Stone goggles ..	Each	18	1 0 0	18
	Total ..	..	..	..	952

Dated 1st August 1933.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M., on 28th August 1933, for restoring Sadalvarapalli Oorumundinakere Regd. No. 718 of Bagepalli Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1934.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees one hundred and fifty in cash or Government Currency Notes, as earnest money, and be superscribed "Tender for restoring Sadalvarapalli Oorumundinakere, Regd. No. 718 of Bagepalli Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders, will be returned.

9. The rates should be entered both in words and figures.

Detailed abstract estimate for restoring Sadalvarapalli Tank Reg. No. 718, Bagepalli Taluk.

No.	Items of work	Per	Quantity	Rate	Amount
<i>Bund.</i>					
1	Earthwork including watering and tamping.	C. yd.	3599	Rs. a. p. 0 4 0	Rs. 900
2	Turfing	S. yd.	3828	0 1 0	239
3	Rough stone revetment new	C. yd.	146	2 0 0	292
4	Do do old	"	168	0 12 0	126
5	Cutting grip in bund to join old and new work.	L. S.	...	...	50
6	Providing and fixing grade and index stones, including cutting and painting figures complete.	Each	25	1 8 0	37
7	Do data stones	"	1	2 8 0	3
8	Do gauge stones	"	1	15 0 0	15
9	Do registered No. stones	"	1	3 0 0	3
10	Do bench mark stones	"	2	3 0 0	6
11	Do constructive detail stones	"	1	25 0 0	25
12	Removing ant-hill and clearing jungle	L. S.	...	...	50
13	Gravel backing to revetment.	C. yd.	134	0 7 0	59
Total rupees to bund					1,805
<i>Sluice.</i>					
1	Repairing the sluice	L. S.	...	...	150
<i>Waste Weir.</i>					
1	Earthwork	C. yd.	606	0 4 0	152
2	Surki concrete	C. ft.	481	0 4 6	135
3	Burnt brick in surki or	"	720	0 5 0	225
3a	Do stone in surki mortar	"	...	...	...
4	Burnt stone slabs 6" thick roughly dressed	S. ft.	662	0 6 0	248
5	Plastering with surki mortar	Sqr.	815	4 0 0	33
6	Rough stone work new	C. yd.	60	2 0 0	120
Total rupees					913